Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.

Schedule - B

Name of the Work : UGD maintenance at kirloskar layout NMH layout & Sahyadri layout in Bagalagunte in ward no. 14

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specification	cum	1282.86	314.95	Rupees Three Hundred Fourteen and Ninety Five Paisa Only
2	Providing and laying in position to required level or slope 300mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications.	cum	900	694.45	Rupees Six Hundred Ninety Four and Fourty Five paisa Only
3	Constructing brick masonry circular type manhole 0.91m internal dia at bottom 0.91 m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3,finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsixe granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diameter confirming IS : 12592, total weight cover and frame to be not less than 182 Kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of machinery, completete as per specifications.(Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid separately) specification	No.s	40	15109.76	Rupees Fifteen Thousand one Hundred and Nine and Seventy Six Paisa only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted	
				In Figures (Rs)	In Words (Rs)
4	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	cum	19.95	7439.70	Rupees Seven Thousand Four Hundred and Thirty Nine and Seventy Paisa Only
5	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	sqm	156	260.42	Rupees Two Hundred and Sixty and Fourty Two Paisa Only
6	Providing & Fixing SFRC Cover and frame 560mm (ID) Heavy Duty..	each	66	1001.6	Rupees One Thousand and One and Sixty Paisa Only
7	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m including cost of all labour complete as specification	cum	1282.86	84.58	Rupees Eighty Four and Fifty Eight Paisa Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner